

KEY

HARDWORKS

- Pearson Park Site Boundary
- Existing buildings within project area
- Proposed new bandstand

SURFACING AND EDGING

- Proposed 'Conservation' concrete road kept to carriage drive (dotted sections indicate dropped kerbs)
- Proposed PCC pin kerb
- Existing blinac to be retained, no work required within this project
- Proposed new full construction blinac
- Proposed resin-bonded gravel surfacing onto blinac path
- Proposed rolled gravel footpath (no path at present)
- Proposed concrete self paving
- Proposed concrete block paving laid as trim (Marshalls Tegula or equal approved)
- Proposed granite setts laid as trim to archway (HCC to provide setts)
- Existing raised rockwork edge to lake to be retained
- Existing rockwork edge to be repaired/ replaced (N.B. Salvaged rocky stone from west of conservatory to be used for lakeside edging stone)

STREET FURNITURE

- Existing bench to be refurbished (3m incl. 2m original benches)
- Proposed bench (7m in main park + 2m in Lodge Garden)
- Proposed hardwood picnic set (3m in main park + 1m in Lodge Garden)
- Proposed entrance welcome sign (4m)
- Proposed litter bin, to match Pearson type (6m)
- Existing Pearson litter bin to be refurbished (6m)
- Proposed bollards (circle indicates removable bollard)
- Proposed cycle rack (5m)
- Proposed footbridge

FENCING

- Existing fence / railing to be retained
- Proposed re-use of salvaged steel railing from site (to bowling green, and to bandstand)
- Proposed new timber fence
- Existing stone plinth to be retained as is (Western boundary)
- Existing gate to be retained
- Proposed gate

E	Street furniture fine lined	✓	CP	SG	05/16
D	Sealing to bandstand adjusted to off peg, free seat omitted, picnic sets and sand sitting added.	✓	CP	SG	05/16
C	Extent of path repairs and shrub planting reduced. Traffic signs added.	✓	CP	SG	05/16
B	Existing green fence added, removal of existing hedge west of conservatory shown.	✓	CP	SG	04/16
A	Crossing point shown, for comment	✓	CP	SG	04/16
Rev.					
CDM	By	Chk	Date		
Proj.	Pearson Park, Hull				
Loc.	HU5 2TQ				

Client:	Hull City Council	southern green chartered landscape architects
Dwg:	Masterplan (Temp Working Layout)	
Scale:	1:1000@A1	
Drawing No.	934 / 1000	Rev. E
		221 Durham Road Low Fell Sunderland NE15 8AB

SOFTWORKS

- Existing tree to be retained (Green Canopy)
 - Existing tree to be removed (Red Canopy)
 - Existing tree to be retained and pruned (Purple Canopy)
 - Proposed tree
 - Proposed Irish Yew trees (Approx. 2m h)
 - Existing ornamental/bedding planting beds to be retained (No work required)
 - Existing shrub groups - to be retained (Rhododendrons, Camellias etc)
 - Proposed new planting bed using salvaged ornamental planting from within the park
 - Proposed new ornamental shrub planting with herbaceous groups
 - Proposed new bedding / herbaceous planting
 - Existing hedge to be retained
 - Proposed hedge
 - Proposed bulb planting
 - Existing amenity grass areas to be retained (and made good after any works)
 - Proposed new grass - seeding
- OTHER
- Potential poetry opportunities, subject to additional funding availability (Provisional Sum Item)
 - Proposed location of flag pole (6m ht in fibreglass) (1m)
 - Proposed sand sifting at 2.5m centres to improve drainage
 - Proposed build up of path level to improve drainage to low spot (Pain R)

